

Accelerating Energy renovation solution for Zero Energy buildings and Neighbourhoods



This project has received funding from the European Union's H2020 Research and Innovation under grant agreement No 768718. The sole responsibility for the content lies with the authors. It does not necessarily reflect the opinion of the European Union.


The EU project RenoZEB in numbers



- Call: H2020-EEB-2017
- 42 months: October 2017 – February 2021
- 19 European partners
- 3 demonstration buildings + 3 virtual demonstration buildings

→ To achieve:

- 16% cost reduction of renovation
- 60% energy consumption reduction
- 65% renovation process time reduction





Background

- Currently only **1.2 % of the building stock** is replaced annually
- To accomplish the 2050 targets increase the rate to **2.9% necessary**
- Currently retrofitting processes are **expensive, complex and disturbing**, with many uncertainties and several inefficacies
- Information is not properly shared, multiple errors and duplicated efforts

RenoZEB strategy:

- technological attractive solutions (**multifunctional modular “plug and play” system**)
- a **well-designed renovation methodology**
- **cloud collaborative environment**
- **involvement** of all key stakeholders
- **property value** as main trigger for nZEB renovation Market



Main Objective

Unlock the nZEB renovation market leveraging the gain on property value through a new systemic approach to retrofitting that will include:

- innovative components
- processes
- decision making methodologies
- to guide all value-chain actors in the nZEB building renovation process


4 main pillars:

- **Reduce energy consumption**, increasing the share of RES in buildings
- **Cost & risk reduction** with low disruption during building renovation, to attract customers interest
- **Replicability and adaptability** through modularity in order to capture a large-scale renovation market
- **Property-value** as trigger



RenoZEB facade - The concept

- **Prefabricated window module** and roller shutter
- **Multifunctional insulation** boards
- Ventilation units with heat recovery
- Building Integrated Photovoltaics (**BIPV**) and batteries
- Building Integrated Solar Thermal Systems (**BIST**)
- **Intelligent façade** controller (integrated sensors and façade controller)
- “**Click-in**” fixing mechanisms



RenoZEB facade - Products selection



Requirements	Proposed Technology/solution			
	1 Compact SA	2 Rbka Compact	3 HELLA TIRIV FRAME	4 TILBEEK Vorwandmontage system
Ventilated facade	N/A	***	N/A	N/A
Plug and play	***	***	***	*
Low-cost multifunctional insulation boards	*	*	*	**
Commercially available PV modules	N/A	N/A	N/A	N/A
Commercially available solar thermal collectors	N/A	N/A	N/A	N/A
"Click in system" for air ducts, heat exchangers for ventilation, pipes and/or electrical or ICT cables	N/A	N/A	N/A	N/A
Integration of hydraulic, electric and HVAC	N/A	N/A	N/A	N/A
Modular, Pre-cast and Easy Assembly-Disassembly	***	***	**	*
minimize on-site work	***	***	***	*
improve product quality	***	***	***	**
reduce costs	**	**	**	*
Industrialization	***	***	***	*
minimize on-site work	***	***	***	*
cost reduction	**	**	**	*
improve quality	***	***	***	*
increased safety	***	***	***	*
Less intrusive system	***	***	**	**
avoid outdoor interventions	***	***	**	**
avoid interruption in the dwellings	***	**	**	***
reduce the duration of the interventions	***	***	***	*
off-site manufacturing	**	***	***	*
plug-and-play solution	**	***	**	*
optimized building processes	**	**	*	*
Aesthetic and functional integration	***	**	**	***
harmonizing architectural rehabilitation with social acceptance	***	*	*	**
expectations of the architect	***	**	**	***
Integration and adaptation of multifunctional insulation	***	***	**	**
use of recycled material	**	**	**	**
reducibility of the final solution	**	**	**	**
reduction of heat and moisture losses	***	***	**	*
fire protection	**	**	**	*
reference to windows installed on facades	***	***	***	*
reduction of heat losses	***	***	***	*
Integration of thermal and PV modules	***	*	*	*
integration into the RenoZEB envelope and building concept solution	***	*	*	*
Connection elements	***	*	*	*
Integrate subsystems in a holistic approach	***	***	**	*
Development of the Smart IoT facade module	N/A	N/A	N/A	N/A
Low-cost sensors	N/A	N/A	N/A	N/A
Low-intrusive installation	N/A	N/A	N/A	N/A
remounting in the module	N/A	N/A	N/A	N/A
Integration with PV and battery system	N/A	N/A	N/A	N/A
Data collection system with common protocols	N/A	N/A	N/A	N/A
Plug & play solution	N/A	N/A	N/A	N/A
Points achieved	22	22	16	17

Prefabricated window module and roller shutter

Requirements	Proposed components		
	1 BIPV semi-transparent	2 BIPV Crystalline partially in glass	3 BIPV crystalline
Ventilated facade	***	***	***
Plug and play	***	***	***
Low-cost multifunctional insulation boards	*	*	*
Commercially available PV modules	***	***	***
Commercially available solar thermal collectors	N/A	N/A	N/A
"Click in system" for air ducts, heat exchangers for ventilation, pipes and/or electrical or ICT cables	***	***	***
Integration of hydraulic, electric and HVAC	**	**	**
Modular, Pre-cast and Easy Assembly-Disassembly	**	**	**
minimize on-site work	***	***	***
improve product quality	**	**	**
reduce costs	**	**	**
Industrialization	***	***	***
minimize on-site work	***	***	***
cost reduction	***	***	***
improve quality	***	***	***
increased safety	***	***	***
Less intrusive system	***	***	***
avoid outdoor interventions	***	***	***
avoid interruption in the dwellings	***	***	***
reduce the duration of the interventions	***	***	***
off-site manufacturing	***	***	***
plug-and-play solution	***	***	***
optimized building processes	**	**	**
Aesthetic and functional integration	**	**	**
harmonizing architectural rehabilitation with social acceptance	**	**	**
expectations of the architect	**	**	**
Integration and adaptation of multifunctional insulation	*	*	*
use of recycled material	*	*	*
reducibility of the final solution	*	*	*
reduction of heat and moisture losses	N/A	N/A	N/A
fire protection	N/A	N/A	N/A
reference to windows installed on facades	N/A	N/A	N/A
reduction of heat losses	N/A	N/A	N/A
Integration of thermal and PV modules	***	***	***
integration into the RenoZEB envelope and building concept solution	***	***	***
Connection elements	***	***	***
Integrate subsystems in a holistic approach	***	***	***
Development of the Smart IoT facade module	***	***	***
Low-cost sensors	N/A	N/A	N/A
Low-intrusive installation	*	*	*
remounting in the module	***	***	***
Integration with PV and battery system	***	***	***
Data collection system with common protocols	N/A	N/A	N/A
Plug & play solution	***	***	***
Points achieved	35	35	35

Building Integrated Photovoltaics (BIPV) and batteries

RenoZEB facade - Building and thermal analysis



Building's boundary conditions

- Existing load bearing structure
- Existing openings

Identification of facade panels:

- Primary panels (window unit)
- Secondary panels (opaque, technical units)
- Eventual aggregation of units





Figure 1: Phase 1 - existing building




Figure 2: Phase 2 - boundary conditions




Figure 3: Phase 3 - identification of baseline




Figure 4: Phase 4a - primary modules designed






Figure 5: Phase 4b - secondary modules designed



Figure 6: Phase 4c - module aggregation design



RenoZEB facade - Units



RenoZEB in demo

DURANGO (Spain)

$$U_{CW} = 0,14 \text{ W/m}^2\text{K} < 0,28 \text{ W/m}^2\text{K}$$


VORU (Estonia)

$$U_{CW} = 0,127 \text{ W/m}^2\text{K} < 0,13 \text{ W/m}^2\text{K}$$

OPAQUE UNIT (max 1200 x 3000 mm)

BASE COMPONENTS:

- Unitized system prefabricated off-site
- Installation on-site on brackets fixed to the slab edge
- Aluminium structure
- Various external finishing
- Mechanical restraint to guarantee the possibility to replace finishings with other materials or technical elements



RenoZEB facade - Units



RenoZEB in demo

DURANGO (Spain)


$U_{CW} = 0,149 \text{ W/m}^2\text{K} < 0,28 \text{ W/m}^2\text{K}$

VORU (Estonia)

$U_{CW} = 0,13 \text{ W/m}^2\text{K} < 0,13 \text{ W/m}^2\text{K}$

PV UNIT (max 1000 x 3000 mm)

- PV integrated in facade with cavity for ventilation to preserve panel efficiency and eventually to use heated air for ventilation



RenoZEB facade - Units



RenoZEB in demo

DURANGO (Spain)

$U_{CW} = 0,139 \text{ W/m}^2\text{K} < 0,28 \text{ W/m}^2\text{K}$


VORU (Estonia)

$U_{CW} = 0,12 \text{ W/m}^2\text{K} < 0,13 \text{ W/m}^2\text{K}$

SOLAR THERMAL COLLECTOR UNIT

(max 2000 x 3000 mm)


- Water thermal solar collector with water to be used also for DHW to have higher water temperature



RenoZEB facade - Prototype




Opaque Unit



Window Unit



PV Unit



Solar Collector Unit







nD Collaborative Environment

Concept

- Objective: to develop a **collaborative environment to integrate deep renovation value chain** around Open BIM standards such as IFC
- Support the digitalization of the whole process and the integration of all actors






nD Collaborative Environment


Architecture

- Cloud platform with public APIs for the integration of any external tool
- The dashboard is the web-based unified portal to access the platform




nD Collaborative Environment

Ongoing work: KPI management




Define KPIs



Select KPIs & define targets



Evaluate scenarios




Define scenarios





nD Collaborative Environment


Ongoing work: IFC viewers



Automatic IFC to
Web GL conversion
(threeJS libraries)

Detailed mode

Building view (with internal navigation)



Georeferenced view
(GIS context)

Automatic IFC to
KML conversion &
web viewing
(cesium libraries)



nD Collaborative Environment

Other functionalities

- Issue management & collaboration

Issues

ID	Name	Description	Type	Status	Created by	Priority	Deadline	Send to	Related data	Actions
407	Create BIM model	Create architectural BIM of Durango	Request	Pending	Manager 1	High	2019-04-25 02:00:00	Architect 1	0	
409	7uk7t6u8o	l78ol	Message	New	Manager 1	Low	-	Architect 1	0	
411	New issue	new issue	Request	Solved	Manager 1	Medium	2019-04-19 02:00:00	Architect 2	0	
413	aaaaa	bbbbb	Incident	Closed	Manager 1	Low	2019-04-20 02:00:00	Architect 2	0	

- Phases/tasks managements

tecnalia Inspiring Business

Admin My projects My issues

Durango demo

- Dashboard
- Users and roles
- Targets
- Scenario manager
- Phases**

Phases

ID	Name	Description	Status	Start	End
313	1 - Plan phase		Finished	2019-03-31	2019-04-29
316	2 - Design phase		In progress	2019-04-30	2019-06-29
317	2.1 - Define Solutions (building level)		In progress	-	-
318	2.2 - Define Solutions (district level)		Not started	-	-
319	2.3 - Cost/Benefit Analysis		Not started	-	-
320	3 - Construction phase		Not started	-	-
322	4 - Management phase		Not started	-	-


Integrated Services



Development of **integrated services** to facilitate **RenoZEB renovation process**:

- **Design Tool** to create the building model.
- **E-catalogue** of renovation solutions
- **Configurator** to help during the design process.
- **Management Tool** for construction and logistics.

BIM Model Generation Tool




Development of an Innovative Data Repository



E-Catalogue: 76 solutions

- **Facade insulation**
- **Floor insulation**
- **Roof insulation**
- **Window systems**
- **Heating and Cooling systems**
- **Ventilation**
- **Photovoltaic panels**



Configurator to design and analyse RenoZEB solutions



IFC BUILDER

<https://www.youtube.com/watch?v=mPHVh95G3YI>



CYPETHERM Eplus

<https://www.youtube.com/watch?v=1a4kQk3l7aM>



POINT CLOUD OPTIMIZATION



CYPETHERM LOADS

<https://www.youtube.com/watch?v=5tShFaCLQ5U>



E-CATALOGUE IMPLEMENTATION



CYPETHERM IMPROVEMENTS

Smart logistic and construction management tool




- READ IFC ENTITIES
- CREATE A QR CODE FOR THAT ENTITY
- ADD INFORMATION TO THE QR CODE
 - DATES
 - PDF, YOUTUBE
- GANNT CHART WITH ALL THE ELEMENTS



Thank you for your attention

Coordinator: Michele Vavallo
michele.vavallo@solintel.eu



This project has received funding from the European Union's H2020 Research and Innovation under grant agreement No 768718. The sole responsibility for the content lies with the authors. It does not necessarily reflect the opinion of the European Union.